



**Additions and Interior Renovations to Gantner,
Gilbert, and 16th Ave. Elementary Schools
D/R Project No. 4132**

February 5, 2024

This Addendum is issued to all Contractors for the purpose of amending the requirements of the Contract Documents, as referred to and noted for the above project, and is hereby made part of said Contract Documents to the same extent as though it were originally included therein. In accordance with laws and the applicable provisions of the Contract Documents, the OWNER hereby issues this Addendum to same. The Contract Documents REQUIRE that each BIDDER acknowledge receipt of this Addendum in the space provided on the Proposal Form. This Addendum shall amend, supplement, and supersede the Contract Documents only as and to the extent explicitly stated herein.

ADDENDUM #7

A. SPECIFICATIONS

1. NO ISSUES

B. DRAWINGS

1. NO ISSUES

C. MISCELLANEOUS

Pre-Bid RFI#5 from B&C Contractors, Inc. Dated February 5, 2024

1. For All 3 ES: The LVT on Finish Schedule A14.2 states that the LVT is 9"x40" and the floor pattern on print A14.1 has a herringbone pattern. As per flooring sub cannot herringbone a 9"x40" Tile, the width has to be evenly divisibly by the length, for example an 9"x36" Tile would work. Please clarify to proceed.
Response: The tiles are 25cmx1m or 9.845"x39.38". The length is divisible by the width. Also, the tile manufacturer lists herringbone as an acceptable installation pattern for this size tile.
2. Page A14.1 Detail's #29 & 30, both have the three colors of LVT but two of them have the same pattern hatching. See attached photo snippet. Please Clarify.
Response: The #5 and #7 callouts are correct. Tag #2 should point to the dark grey hatch and tag #3 should point to the light grey hatch in both instances.
3. Addendum # 03 (A-7) states delete spec section 12492, but it has been reissued with combined manual & electrical shade. Please confirm Spec 12240 should be deleted.
Response: Delete originally issued sections 12492 and 12240 and replace both with section 12492 (misnamed as 12240) issued in Addendum #3.



Pre-Bid RFI#2 from M&M Construction, Dated February 5, 2024

1. The LVT on Finish Schedule A14.2 states that the LVT is 9"x40" and the floor pattern on print A14.1 has a herringbone pattern. Unfortunately, you cannot herringbone a 9"x40" Tile, the width has to be evenly divisible by the length, for example 9"x36" Tile would work. Please advise.

Response: See question #1 above under B&C Contractors, Inc. RFI#5.

END OF ADDENDUM #7